Plot 3C-2, Ananthapuram Development Plot, Kasaragod, Kerala.
+91 83 4007 4006 · mail@ourownrm.com

OUR OWN READY-MIX
CONCRETE MIX DESIGN

IS:10262-2019 | IS:456-2000 | IS 4926:2003

MIX GRADE	DESIGN REF. CODE	REVISION	STATUS
M25	OR20F207	0	APPROVED

MIX DESCRIPTION	CREATED	APPROVED
General Purpose Concrete — Standard Grade	20 Jul 2026 Pallavi Nandakumar	21 Jul 2026 Quality Control Engineer

MIX DESIGN SUMMARY

Compressive Strength (f'ck) at 28 days **25.0 MPa**	Standard Deviation (SD) **4.0 MPa**	Maximum Aggregate Size **20 mm**
Target Mean Strength (f'ck + 1.65 x SD) **31.6 MPa**	Free Water / Binder Ratio (W/B) **0.450**	Water Content **158 kg/m3**
Total Binder (Cement + Fly Ash) **351 kg/m3**	Target Workability at Site **100-125 mm (Slump)**	Design Density **2,480 kg/m3**

MIX PROPORTIONS (SSD/m3)

Cement	**320** kg/m3
Fly Ash (PFA) — 9% of Binder	**31** kg/m3
Total Binder (Cement + Fly Ash)	**351** kg/m3
Free Water Content	**158** kg/m3
Free Water / Binder Ratio (W/B)	**0.450**
Fine Aggregate	**720** kg/m3
Coarse Aggregate — 20 mm	**650** kg/m3
Coarse Aggregate — 12.5 mm	**460** kg/m3
Total Aggregate	**1,830** kg/m3
Admixture — Sika ViscoCrete 3000, 0.60% of Binder	**2.10** kg/m3
Design Density	**2,480** kg/m3

MATERIALS — TYPE / SOURCE / SP. GR.

MATERIAL	TYPE / SOURCE	SP.GR.
Cement	OPC 53 Grade / Dalmia Cement / Ramco Cements Ltd (approved vendor list)	3.15
Fly Ash (PFA)	Class F Fly Ash / NTPC Kayamkulam Thermal Plant	2.20
Fine Aggregate	M-Sand / Local Quarry, Kasaragod	2.65
Coarse Aggregate — 20 mm	Crushed Granite 20mm / Local Quarry, Kasaragod	2.70
Coarse Aggregate — 12.5 mm	Crushed Granite 12.5mm / Local Quarry, Kasaragod	2.70
Admixture	Sika ViscoCrete 3000	1.09
Maximum Aggregate Size	20 mm	—

AGGREGATE PROPORTIONS

FRACTION	QTY (kg/m3)	% OF TOTAL
Fine Aggregate	720	39%
Coarse — 20 mm	650	36%
Coarse — 12.5 mm	460	25%
Total	**1,830**	**100%**

Coarse / Fine Aggregate Ratio

COARSE 61% | FINE 39%

Aggregate Proportion



- M-Sand (fine) — 39%
- 20 mm (coarse) — 36%
- 12.5 mm (coarse) — 25%

NOTE

1. Admixture dosage to be adjusted based on ambient temperature and transport time.
2. Moisture correction of aggregates to be carried out daily.
3. All quantities are in SSD condition unless specified.

Quality Control Engineer
Quality Control, Our Own Ready Mix

Disclaimer: This mix design has been prepared in accordance with applicable Indian Standards based on laboratory trials and the materials specified herein. Actual field performance is dependent upon proper batching, transportation, placement, compaction, finishing, curing and site conditions. Any change in material source or characteristics may require review and revision of the mix design.